Legend

1. Forpark basket 'Pendulum swing' with Play Matta access and bark mulch.
2. Large 'climbing' rocks 500mm max. high in turf.
3. New granitic path around edge of play space.
4. Renovate existing equipment as required.
5. New Play Matta base to existing swings - brightly coloured to match equipment.
6. Relocated two toddler rockers.
7. Forpark 'Twin peaks' rope climbing structure.
8. Winding path of flat rock stepping stones.
9. Rubber soft fall mound to ramp up to flying fox.
10. Timber pole 'Forest' - Brightly painted.
11. Extend bark play space with semi-circle of seating rocks.
12. Renew Bayside seats with timber versions.
13. Existing trees to be retained.
14. Top up play bark mulch as required.

Existing trees to be retained

Existing grass to be retained

Existing shrub to be retained

Plan

epcad.com.au

Bayside City Playgrounds

Ashwood Avenue Concept Plan

N

SCALE 1:100 M

scale : 1 : 100 @ A1 date : 15 July 2020

EPCAD Pty Ltd ACN 093 476 334 ABN 26 093 476 334
28-30 Mayfair Street, West Perth, WA 6005. PO Box 1233, West Perth WA
☎+61 8 9481 4410 ✉epcad@epcad.com.au

EPCAD



Play equipment / furniture

Paving palette

EPCAD Pty Ltd ACN 093 476 334 ABN 26 093 476 334
28-30 Mayfair Street, West Perth, WA 6005. PO Box 1233, West Perth WA
☎+61 8 9481 4410 ✉epcad@epcad.com.au

EPCAD